MS.ID-IJPBS-6342
International Journal of Pharmacy and Biological Sciences-IJPBS™ (2026) 16 (4): 01-07
Online ISSN: 2230-7605, Print ISSN: 2321-3272
Review Article | Pharmaceutical Sciences | OA Journal | MCI Approved | Index Copernicus

Rotary Evaporator Qualification: A Systematic Approach to Design, Installation, Operation, And Performance: A Review

Gambo Nikitha[1], Rojaramani Nakka[2], Siva Jyoti Buggana[3], and Mamatha Tirunagari*

[1]Department of Pharmaceutical Quality Assurance, Sarojini Naidu Vanita Pharmacy Maha Vidyalaya (Co.Ed) Hyderabad, Telangana, India -500017.
[2]Department of Pharmaceutical Quality Assurance, Sarojini Naidu Vanita Pharmacy Maha Vidyalaya (Co.Ed) Hyderabad, Telangana, India -500017.
[3*]Department of Pharmaceutical Quality Assurance, Sarojini Naidu Vanita Pharmacy Maha Vidyalaya (Co.Ed) Hyderabad, Telangana.India -500017.

Received: 29 May 2026/ Accepted: 2 Jun 2026 / Published online: 1 Oct 2026
***Corresponding Author Email:** tmamathasnvpmv@gmail.com

Abstract

Rotary evaporation is widely used for solvent removal, sample concentration, purification-related laboratory operations and solvent recovery under reduced pressure. Because performance depends on the coordinated control of vacuum, temperature, rotation and condensation, qualification is important for demonstrating that the equipment is suitable, reliable and safe for its intended use. This review summarizes the operating principle, major components, applications, safety considerations and lifecycle qualification of rotary evaporators, with emphasis on design qualification (DQ), installation qualification (IQ), operational qualification (OQ) and performance qualification (PQ). A structured review of the qualification concepts and equipment requirements described in pharmaceutical quality guidance and laboratory literature was used to organize the discussion. DQ establishes suitability of the selected design against predefined user requirements; IQ verifies installation, utilities, components and documentation; OQ challenges critical functions such as rotation, heating, vacuum, cooling, lifting, controls and safety systems; and PQ demonstrates integrated performance under representative operating conditions. Critical performance considerations include vacuum stability, temperature and rotation control, condensation efficiency, evaporation behaviour, solvent recovery and reproducibility. Requalification, calibration, maintenance, change control and deviation management are also considered as part of lifecycle management. Qualification limits should be scientifically justified and linked to intended use and equipment specifications rather than treated as universal values. A documented, risk-based qualification programme can therefore provide continued assurance of safe and consistent rotary-evaporation performance in pharmaceutical and laboratory environments.

Keywords

Equipment qualification; Performance qualification; Rotary evaporator; Risk-based qualification

*****

1. INTRODUCTION

Rotary evaporation is a laboratory technique for controlled removal of volatile solvents under reduced pressure. A rotary evaporator combines vacuum, controlled heating and flask rotation to lower the boiling temperature of a solvent and improve heat and mass transfer. It is used for solvent removal, concentration, purification-related

laboratory operations and solvent recovery. The major components generally include an evaporating flask, heating bath, rotation system, vapour duct, condenser, receiving flask, vacuum system and lifting mechanism.

During operation, the sample-containing flask is rotated while partially immersed in a heated bath. Rotation distributes the liquid as a thin layer over the internal flask surface, increasing the effective evaporation area. Reduced pressure lowers the solvent boiling point, while the condenser removes heat from the vapour and converts it into liquid for collection. Stable control of bath temperature, vacuum, rotation speed and condenser temperature is therefore important for reproducible evaporation [1,2].

In pharmaceutical and laboratory quality systems, equipment qualification provides documented evidence that equipment is appropriately selected or designed, correctly installed, operates within predefined limits and performs its intended function. Qualification is generally organized through DQ, IQ, OQ and PQ, supported by calibration, maintenance, change control, deviation management and, where justified, requalification.

The extent of qualification should be proportionate to equipment criticality, intended use, manufacturer's recommendations and applicable quality requirements.

The purpose of this review is to consolidate the principles, components, operation, applications, safety considerations and qualification activities associated with rotary evaporators, with particular emphasis on the DQ-IQ-OQ-PQ lifecycle. The article also identifies critical parameters that should be considered when establishing scientifically justified acceptance criteria [3,4].

2. WORKING PRINCIPLE AND MAJOR COMPONENTS

The working principle of a rotary evaporator is based on the reduction of solvent boiling temperature under reduced pressure. The vacuum system lowers the pressure within the evaporation assembly, allowing solvent vaporization at a lower temperature than would be required at atmospheric pressure. Simultaneously, rotation spreads the liquid over the flask wall and improves heat and mass transfer. Vapour generated from the evaporating flask passes through the vapour duct to the condenser and is collected in the receiving flask.

The evaporating flask holds the material being concentrated, while the heating bath provides controlled thermal energy. The motor and drive assembly maintain flask rotation. The condenser provides a cooled surface for solvent condensation, and the receiving flask collects the condensed solvent. The vacuum system, tubing, seals and valves establish and maintain reduced pressure. A lifting mechanism permits controlled positioning of the evaporating flask and contributes to safe operation. Modern instruments may incorporate digital displays, programmable operation, automated vacuum regulation, monitoring functions and safety features.

3. APPLICATIONS

Rotary evaporators are used in pharmaceutical research for concentrating extracts and solutions, removing solvents following synthesis and preparing samples for subsequent analytical or formulation work. Reduced-pressure operation can be useful when processing materials for which unnecessary exposure to high temperatures is undesirable.

- In chemical laboratories, rotary evaporation is used for solvent removal, concentration and solvent recovery.
- In natural-product and food-related research, it can be used for concentrating extracts, flavor or volatile fractions and other laboratory preparations.
- Environmental and analytical laboratories may use rotary evaporation as a sample-concentration step before instrumental analysis. The equipment is also useful as a general laboratory tool because solvent recovery can reduce waste and improve resource utilization.

4. QUALIFICATION OF ROTARY EVAPORATOR

The qualification of a rotary evaporator (Rotavap) is a systematic and documented quality assurance process carried out to establish that the equipment has been appropriately designed or selected, correctly installed, operates within its specified limits, and consistently performs its intended function. Qualification provides documented evidence that the equipment is suitable for its intended application and is capable of delivering reliable, reproducible, and safe performance under defined operating conditions.

Rotary evaporators are widely used in pharmaceutical, chemical, biotechnology, analytical, and research laboratories for the concentration of solutions, removal of volatile solvents, solvent recovery, and preparation of samples. The evaporation process generally takes place under reduced pressure, which lowers the boiling point of the solvent and permits evaporation at comparatively lower temperatures. This is particularly useful for heat-sensitive substances.

The performance of a rotary evaporator is dependent on the coordinated operation of several critical components, including the heating bath, rotating drive system, evaporating flask, condenser, receiving flask, vacuum system, cooling system, lifting mechanism, seals, control system, and associated accessories. Therefore, these components and their relevant functions should be evaluated during the qualification process [5,6,7].

The qualification lifecycle is generally structured according to the following stages:

1. Design Qualification (DQ)
2. Installation Qualification (IQ)
3. Operational Qualification (OQ)
4. Performance Qualification (PQ)

The extent of qualification should be based on the intended use of the equipment, its criticality, applicable quality requirements, manufacturer's recommendations, and the laboratory's established procedures.

Table 1. Major stages of rotary-evaporator qualification.

Stage	Purpose	Representative activities
DQ	Confirm design suitability	URS review; material compatibility; heating, rotation, vacuum, cooling, safety and utility requirements
IQ	Confirm correct installation	Equipment identification; component verification; utilities; location; physical inspection; documentation
OQ	Confirm functional operation	Rotation; temperature; vacuum; condenser; lifting; alarms; safety; controls
PQ	Confirm integrated performance	Evaporation; solvent recovery; vacuum stability; condensation; reproducibility; process observation

Table 2. Critical parameters and qualification focus.

Parameter	Qualification focus	Representative evidence
Heating temperature	Accuracy, stability, response and protection	Calibrated reference measurement and alarm challenge
Rotation speed	Set-point achievement and mechanical stability	Calibrated reference measurement and observation
Vacuum	Achievement, stability and leakage control	Pressure measurement and leak/hold test
Condenser/cooling	Cooling stability and condensation	Temperature/circulation verification and process observation
Safety functions	Alarm, stop and protection responses	Predefined functional challenge tests
PQ performance	Integrated evaporation and recovery	Representative runs and predefined acceptance criteria

Table 3. Typical qualification documentation.

Record	Purpose
URS/DQ	Defines requirements and demonstrates design suitability
IQ/OQ/PQ protocols and reports	Documents installation, functional and performance verification
Calibration certificates	Provides measurement assurance
Deviation/CAPA records	Documents investigation and corrective action
Change-control records	Assesses impact of modifications
Maintenance/logbook	Provides lifecycle traceability
Qualification summary report	Provides final qualification and release conclusion

4.1. Design Qualification [DQ]

Design Qualification is a documented assessment confirming that the proposed design or selected rotary-evaporator model is appropriate for its intended application and satisfies the approved User Requirement Specification before procurement and routine operation. The assessment compares user requirements with manufacturer or supplier specifications and documents discrepancies, technical justification and risk assessment where required.

The URS may define evaporating- and receiving-flask capacities, rotation-speed range, heating-bath range and control, vacuum requirements, condenser and

cooling requirements, lifting mechanism, automation, alarms, material compatibility, electrical supply, safety functions and documentation. Requirements should reflect actual laboratory applications and anticipated workload rather than generic specifications.

Material compatibility should be assessed for glassware, seals, gaskets, tubing, valves and other components exposed to samples, solvents or vapours. Vacuum requirements should address pressure range, stability, pump capacity, control mechanism, tubing and leakage control. Heating requirements should address temperature range, accuracy, stability, response, uniformity and over-temperature protection. Rotation requirements should include an appropriate operating range, speed-control accuracy, smooth operation and acceptable mechanical behaviour.

The proposed installation area should also be assessed for bench stability, vertical clearance, electrical supply, grounding, ventilation, fume extraction, vacuum and cooling utilities, and access for cleaning and maintenance. DQ approval should demonstrate that the selected equipment can meet the intended technical, operational, safety and quality requirements [5,6].

4.2. Installation Qualification [IQ]

Installation Qualification verifies that the rotary evaporator, its accessories and required utilities have been received, identified, inspected, installed and connected according to approved specifications and manufacturer instructions. Equipment identification should include manufacturer, model, serial number, equipment identification number, installation date, location and relevant procurement information.

All supplied components should be checked for completeness and physical condition. Depending on configuration, these may include the evaporating flask, receiving flask, condenser, heating bath, rotation assembly, drive motor, vacuum equipment, cooling system, seals, gaskets, adapters, tubing, clamps, control unit and safety accessories. Installation should be inspected for cracks, chips, damaged seals or tubing, loose connections, electrical damage and missing components.

Utilities should be verified against manufacturer requirements. Electrical supply, grounding, vacuum connections, cooling-water or chiller connections and ventilation should be documented. The equipment should be located on a stable, level surface with sufficient access for operation, cleaning, maintenance and emergency intervention. Required documentation may include the equipment manual, specifications, URS, certificates, calibration records, installation records, maintenance information, equipment logbook and approved SOPs.

Successful IQ provides documented evidence that the equipment is correctly installed and ready for operational testing. Equipment-specific numerical values, such as temperature range, rotation range, chiller capacity or pump performance, should be taken from the approved model specification rather than presented as universal qualification requirements [7].

4.3. Operational Qualification [OQ]

Operational Qualification verifies that the rotary evaporator and its critical functions operate correctly and consistently within specified operating ranges. Testing should be performed using an approved protocol with predefined procedures and acceptance criteria.

Rotation speed should be challenged at selected operating points using an appropriate calibrated reference instrument. The test should confirm achievement of the selected speed, smooth operation and absence of unacceptable vibration or abnormal noise. Heating-bath performance should be assessed at selected low, intermediate and high settings using a calibrated temperature reference. Accuracy, stability, heating response, control performance, over-temperature protection and alarms should be verified.

Vacuum performance should be assessed for achievement and maintenance of the required pressure. Leakage, tubing, seals, valves and pump performance should be considered. The condenser and cooling system should be checked for coolant circulation, temperature stability, leakage and effective condensation. The lifting mechanism should operate smoothly through its intended range, and automated lifting functions should be challenged where provided [8,9].

Safety functions may include emergency stop, over-temperature cut-off, alarm functions, motor protection, lift safety, vacuum protection and power-failure responses. Digital control functions may include display and adjustment of heating temperature, rotation speed, process time, flask position, lift speed, vapour temperature, vacuum conditions and process status. Where solvent libraries, presets, seal monitoring or other automated functions are provided, these should be verified according to their intended use.

The OQ should document any failure or unexpected result through the applicable deviation-management process. The impact on qualification should be assessed and corrective or preventive action initiated where required. OQ acceptance criteria should be

linked to approve equipment specifications and intended use.

4.4. Performance Qualification [PQ]

Performance Qualification (PQ) was carried out to demonstrate that the rotary evaporator consistently performs solvent evaporation effectively under defined operating conditions using a synthesized chemical sample. The study was performed after satisfactory completion of DQ, IQ and OQ.

For the PQ study, the synthesized chemical sample containing different solvents, namely methanol, dichloromethane, ethanol and water, was subjected to solvent evaporation using the rotary evaporator. The evaporation studies were performed under predefined operating conditions, including water-bath temperature, rotation speed, vacuum pressure, condenser cooling and evaporation time, as appropriate for each solvent [9,10].

The performance of the rotary evaporator was evaluated based on the time required for solvent evaporation, stability of vacuum and temperature, efficient condensation and collection of the evaporated solvent, and reproducibility of the evaporation process. The equipment was also monitored for any abnormal observations such as excessive bumping or foaming, leakage, unstable rotation, vibration, unusual noise, pressure fluctuations, vapour release, poor condensation or heating instability.

The PQ was considered satisfactory when methanol, dichloromethane, ethanol and water were effectively evaporated from the synthesized chemical sample without significant operational abnormalities and with stable equipment performance. The results demonstrated that the rotary evaporator was suitable for its intended laboratory application of solvent removal and concentration of synthesized chemical samples [11,12].

Fig No: 1 Working of Rotary Evaporator

5. CRITICAL PARAMETERS AND RISK-BASED QUALIFICATION

A risk-based approach allows qualification effort to focus on functions that have the greatest potential to affect process performance or safety. For rotary evaporation, critical parameters may include bath temperature, rotation speed, vacuum level and stability, condenser temperature and cooling performance, evaporation behaviour, solvent recovery and leakage control.

Risk assessment should consider the intended solvent system, sample sensitivity to heat, expected operating range, equipment configuration, safety hazards and consequences of failure. Higher-risk functions may require more detailed testing or tighter acceptance criteria, while lower-risk functions may be addressed through supplier documentation, inspection or routine maintenance when justified. The qualification protocol should explain why each test is performed, how it is measured, what criterion applies and how failures are managed [13,14].

6. REQUALIFICATION AND LIFECYCLE MANAGEMENT

The qualified state should be maintained throughout the equipment lifecycle through calibration, preventive maintenance, monitoring, deviation management, change control and periodic review. Requalification should be considered following major repair, replacement of critical components, relocation, significant hardware or software modification, changes in operating range or other events that could affect qualified performance.

The extent of requalification should be based on documented impact assessment and risk rather than

automatically assuming that a complete qualification is required for every event. Periodic review may consider previous qualification results, calibration and maintenance history, breakdowns, deviations, operating changes and performance trends. Depending on the outcome, partial verification or complete IQ/OQ/PQ may be justified [15,16,17].

Fig No: 2 Rotary Evaporator

Fig No:3 Chiller and Vaccum pump

7. QUALIFICATION DOCUMENTATION

Qualification records should provide traceability from the original requirement through equipment selection, installation, testing, release and lifecycle maintenance. Typical records include the URS, DQ, IQ, OQ and PQ protocols and reports, equipment specifications and manuals, identification records, calibration certificates, utility verification, raw data, acceptance criteria, deviation and investigation records, CAPA where applicable, change-control records, preventive-maintenance records, equipment logbook and the final qualification summary report.

Raw data should remain traceable to the equipment, test date, operator, measuring instrument and calibration status. Unexpected results and deviations should be documented, scientifically assessed and resolved before routine release where they could affect qualification. The final qualification report should summarize the activities, results, deviations, corrective actions and conclusion regarding the qualified status [18,19].

8. CONCLUSION

Qualification of a rotary evaporator provides documented evidence that the equipment is suitable for its intended purpose, correctly installed, operationally reliable, and capable of delivering consistent performance under defined operating conditions. A systematic qualification approach generally progresses through Design Qualification (DQ), Installation Qualification (IQ), Operational Qualification (OQ), and Performance Qualification (PQ). DQ establishes that the selected equipment design and specifications are appropriate for the intended application and comply with predefined user requirements. IQ verifies the correct installation of the equipment, its major components, utilities, associated accessories, and relevant documentation. OQ evaluates critical operational functions, including heating, rotation speed, vacuum generation and control, cooling and condensation, lifting mechanisms, alarms, and safety systems. PQ provides documented evidence that the integrated system performs consistently and reproducibly under representative routine operating conditions.

Maintaining the qualified state is an essential component of the equipment lifecycle and should include appropriate calibration, preventive maintenance, change control, deviation management, periodic performance review, risk assessment, and requalification whenever justified by changes or performance trends. A structured, science- and risk-based qualification programme can strengthen confidence in evaporation efficiency, solvent recovery, temperature and vacuum control, operational consistency, and laboratory safety. In addition, continued advances in digital monitoring,

automated process control, electronic data recording, and equipment diagnostics may provide opportunities for improved process oversight and lifecycle management. However, such computerized and automated functions should be appropriately assessed, qualified, controlled, and maintained in accordance with applicable quality and data-integrity requirements. Overall, a well-designed qualification programme provides a systematic framework for demonstrating the reliability, reproducibility, and fitness-for-purpose of rotary evaporators in pharmaceutical and laboratory applications [19].

9. ACKNOWLEDGEMENTS:

The authors would like to express their sincere gratitude to the management and the Department of Pharmaceutical Quality Assurance, Sarojini Naidu Vanita Pharmacy Maha Vidyalaya (Co-Ed), Hyderabad, Telangana, India, for providing the institutional support and facilities necessary for the preparation of this review article. The authors also acknowledge the valuable support and encouragement provided by the faculty members and colleagues during the preparation of the manuscript.

REFERENCES:

[1]. Mamatha Tirunagari, Raheem MD. Qualification of Equipment: Bin Blender and Compression Machine. Journal of Drug Delivery and Therapeutics. 2(3):(2012)

[2]. Mamatha Tirunagari, Nasreen Shaik. Qualification of equipment: Saizoner mixer granulator and automatic coating machine (Neocota). Der Pharmacia Sinica (Pelagia Research Library). 3(5):561-568 , (2012)

[3]. Anuradha Bai.S, G. Deekshitha, G. Niharika. Autoclave qualification: assuring sterility and product quality in pharmaceutical operations. Degres Journal. 10(9):262 , (2025)

[4]. World Health Organization: Annex 2 – WHO good practices for pharmaceutical microbiology laboratories. WHO Tech Rep. 961:69-93, (2011)

[5]. International Council for Harmonisation (ICH). ICH Q9(R1): Quality Risk Management. (2023).

[6]. International Council for Harmonisation (ICH). Q7: Good Manufacturing Practice Guide for Active Pharmaceutical Ingredients. Section 12.3, Qualification, directly defines DQ, IQ, OQ and PQ and discusses qualification of critical equipment before process validation.

[7]. European Commission. EudraLex Volume 4, EU Guidelines for Good Manufacturing Practice for Medicinal Products, Annex 15: Qualification and Validation.

[8]. U.S. Food and Drug Administration. Process Validation: General Principles and Practices. Guidance for Industry. January (2011).

[9]. United States Pharmacopeia : Analytical Instrument Qualification. USP–NF. General Chapter :1058:(2025).

[10]. Burgess C, Weitzel MLJ, Roussel JM, et al. Analytical Instrument and System (AIS) Qualification, to Support Analytical Procedure Validation over the Life Cycle. Pharmacopeial Forum. (2022).

[11]. Anuradha Bai. Sandala. Sowmya.B. Challenges and Solutions for Dissolution Equipment Qualification. Journal of Dalian University of Technology. 32(11):1402-1410 , (2025)

[12]. Webster GK, Kotts L, Maloney TD. Considerations When Implementing Automated Methods into GxP Laboratories. Journal of Automated Methods and Management in Chemistry / JALA. (2005).

[13]. Schafer W, et al. Efficient and economic HPLC performance qualification. Journal of Pharmaceutical and Biomedical Analysis. (2010).

[14]. Hoffman RV. The construction of an inexpensive rotary evaporator. Journal of Chemical Education. 53(7):459 , (1976)

[15]. Maynard DF. A Microscale Rotary Evaporator. Journal of Chemical Education. 71(11):A272 , (1994)

[16]. Stankiewicz AI. Heat transfer in thin-film wiped-surface evaporation of model liquid foods. Journal of Food Process Engineering. (1988).

[17]. Frank JT, Lutcha J. Thickness of the film of material treated in a film-type rotary evaporator. International Chemical Engineering. 20(1):65–76 , (1980)

[18]. Chatterjee S, Sugilal G, Prabhu SV. Heat transfer in a partially filled rotary evaporator. International Journal of Thermal Sciences. 142:407–421,(2019)

[19]. Ostrove S. Equipment Qualification in the Pharmaceutical Industry. Academic Press; 2019.